

November 11, 2025

Marshville Municipal Park Baseball, Softball and Tennis Project #248423

Marshville, North Carolina

Sourcewell Quotation Price – Turnkey Installation

Baseball 300' radius 50/30 footcandles, Softball 190' radius 50/30 footcandles, Softball 200'/225'/200' irregular radius 50/30 footcandles and 3 court Tennis/Basketball combo 50 footcandles

Musco Materials per field description, security camera electrical enclosures and pole modifications to accommodate.....	\$ 707,000
Installation per scope providing 35% MWBE contribution by a NC certified MWBE contractor, signed and sealed electrical drawings, permitting.....	\$ 395,000
USE tax estimate.....	\$ 23,000
Total.....	\$1,125,000

Light-Structure System™ with Total Light Control – TLC for LED™ technology

Musco's Light Structure Green System provides 25 years of safe, guaranteed light levels at the lowest operating cost in a hassle free manner by eliminating 100% of the maintenance and communication costs.

- Musco is the manufacturer and directly responsible for the production and performance of their lighting systems.
- This is a quality UL Listed lighting system – designed with enclosed wiring, and remote ballasts for maintenance and easy fuse inspection.
- This system maintains the integrity of the light for 25 years of guaranteed maintained light levels with our patented Constant Light Technology.
- All maintenance associated with the lighting system including labor and materials covered by Musco's Constant 25 years warranty.
- Musco provides specifically funded reserves to assure owners of their ability to back up the performance claims and maintenance.
- Musco provides testing and accountability throughout warranty period
- Musco Sports Lighting is the only manufacturer with dedicated field service/maintenance staff with a local office.
- Control Link internet-based control and monitoring system provides the most comprehensive values/features. All communication costs are included during the warranty period.
- Glare and spill light control is reduced by at least 50% compared to conventional light technology as specified through improved photometrics and proper mounting height design.

System Description

- Total Light Control™ TLC-LED factory-aimed and assembled luminaires
- BallTracker® technology – targeted light, optimizing visibility of the ball in play with no glare in the players typical line-of-sight



Quote

- Galvanized steel poles
- Pre-cast concrete bases with integrated lightning grounding
- Pole length factory assembled wire harnesses
- Factory wired and tested remote electrical component enclosures
- UL listed assemblies

Notes

- Union County Sourcewell member #27270
- Sourcewell Master Project: 199030, Contract Number: 041123-MSL, Expiration: 06/16/2027 Category: Sports lighting with related supplies and services.
- All purchase orders should note the following: Sourcewell Purchase – Contract Number: 041123-MSL
- Includes signed and sealed foundation drawings based on standard soils
- Assumes standard soil conditions – rock, bottomless, wet, or unsuitable soil may require additional engineering, special installation methods and additional cost.
- Includes signed and sealed electrical drawings
- Includes permitting costs
- Includes applicable USE taxes
- Timing of installation based on date that executed contract is received.
- Quote is confidential.
- Pricing valid until 12-31-25.

Thank you for considering Musco for your lighting needs. Please contact me to review any questions or if you need additional details.



Dina Neeley
North Carolina Senior Lighting Consultant
Musco Sports Lighting, LLC
336.414.1030
dina.neeley@musco.com





North Carolina
Department of Administration
Office for Historically Underutilized Businesses

Gabriel J. Esparza
Secretary

Alicia Lyon
Director

6/6/2025

Sara Cane

Certification Number: HUB-366616
Newco Electric, LLC. (Female Owned)
6135 Ashland Rd.
Kannapolis, North Carolina 28083

Dear Sara Cane:

The Office for Historically Underutilized Businesses (HUB Office) is pleased to inform you that your company is now certified as a Historically Underutilized Business. Your firm is listed in the Statewide Uniform Certification (SWUC) Program database. This HUB certification remains in effect for a duration of 4 years.

You must notify the HUB Office in writing within 30 days of any changes affecting your compliance with SWUC Program eligibility requirements, including changes in ownership, day-to-day management and operational control. Failure to notify the HUB Office of these changes or reapply for certification in a timely manner may cause your HUB Certification to be revoked. In addition, please be advised your status may be changed if there is a 3rd party challenge granted against your firm. The link to the HUB Office 3rd party challenge form can be located at [Third Party Challenge Form](#). All information submitted to the Office for Historically Underutilized Business is subject to audit and review.

The HUB Office collaborates with local Minority/Women/Small Business (M/W/SBE) Offices who offer assistance to certified HUB firms with identifying contract opportunities with state and local government. Many of these offices also offer assistance with business development. Please visit our website at <https://www.doa.nc.gov/divisions/historically-underutilized-businesses-hub/resources/state-local-contracting> to locate the local office near you.

It is important to note that although your status as a certified HUB firm can improve your access to state and local government contracts, this certification does not guarantee contract awards. Your ability to research opportunities and bid competitively will be important to your success in this program. We are committed to assisting you through the process. We provide training and resource materials to assist vendors in navigating state government solicitations. Visit our web site for more information at [NC DOA Historically Underutilized Businesses \(HUB\) Office - Minority, Women-Owned & Small Businesses](#).

Thank you for your interest and participation in the SWUC Program as a Historically Underutilized Business firm with the State of North Carolina.

Sincerely,

Alicia Lyon

Alicia Lyon
Director



Marshville Municipal Park Scope of work

Field #1 Scope of work

Musco LSG System

- Receive, offload, store, layout, assemble, erect, ground and terminate.
- Demo & dispose of 6 existing wood poles/fixtures.

Electrical Service scope

- Use existing, 200-amp, 120/208-volt, 3-Phase, underground.
- Build a new galvanized free-standing rack.
- Add Musco LCC.
- Add new circuit breakers as needed.

Branch Circuits

- One to each Musco light pole.
- One, 20A/120v circuit to Pole B1 security camera.
- PVC or HDPE conduit, Schedule 40.
- Copper wire.

Field #2 Scope of Work

Musco LSG System

- Receive, offload, store, layout, assemble, erect, ground and terminate.
- Demo & dispose of 6 existing wood poles/fixtures.

Electrical Service:

- Use existing tennis service, 200-amp, 120/208-volt, 3-Phase, underground.
- Build a new galvanized free-standing rack.
- Add new 100A sub-panel.
- Add Musco LCC.
- Add new circuit breakers as needed.

Branch Circuits

- One to each Musco light pole.
- One, 20A/120v circuit to Pole A1 security camera.
- PVC or HDPE conduit, Schedule 40.
- Copper wire.

Field #3 Scope of Work

Musco LSG System

- Receive, offload, store, layout, assemble, erect, ground and terminate.
- Demo & dispose of 6 existing wood poles/fixtures.

Electrical Service:

- Use existing, 200-amp, 120/208-volt, 3-Phase, overhead.
- Build a new galvanized free-standing rack.
- Add Musco LCC.
- Add new circuit breakers as needed.



Branch Circuits

- One to each Musco light pole.
- One, 20A/120v circuit to Pole B1 security camera.
- PVC or HDPE conduit, Schedule 40.
- Copper wire.

Tennis/Basketball Scope of Work

Musco LSG System

- Receive, offload, store, layout, assemble, erect, ground and terminate.
- Demo & dispose of 4 existing wood poles/fixtures.

Electrical Service:

- Use existing, 200-amp, 120/208-volt, 3-Phase, underground.
- Build a new galvanized free-standing rack.
- Add new 100A sub-panel for Softball Field #2.
- Add Musco LCC.
- Add new circuit breakers as needed.
- Add player activated courtside pushbutton controls

Branch Circuits

- One to each Musco light pole.
- One, 20A/120v circuit to Pole T3 security camera.
- PVC or HDPE conduit, Schedule 40.
- Copper wire.

